

BERWICK RETAINING WALL

Master Business Knowledge Base, Sales Manual & Operations Manual

Business: Berwick Retaining Wall

Industry: Retaining Wall Construction & Installation

Location: Berwick, Victoria, Australia

Business Model: Supply & Install + Installation Only

Experience: 20 years

Data Status: All business information, policies and prices in this document are fictional and created for business/AI training purposes.

1. BUSINESS PROFILE

Business Name

Berwick Retaining Wall

Business Description

Berwick Retaining Wall specialises in the construction and installation of retaining walls for residential and small commercial properties.

The business can either:

Option A — Supply & Install

Berwick Retaining Wall purchases the required materials and completes the retaining wall installation.

Option B — Installation Only

The customer purchases and supplies the retaining-wall materials, while Berwick Retaining Wall provides the labour and installation.

Services can include:

- Timber sleeper retaining walls
- Concrete sleeper retaining walls
- Steel post retaining walls
- Timber post retaining walls
- Garden retaining walls
- Boundary retaining walls
- Tiered retaining walls
- Replacement retaining walls

- Retaining wall repairs
 - Existing wall removal
 - Excavation
 - Post-hole excavation
 - Concrete footings
 - Drainage installation
 - Backfilling
 - Gravel installation
 - Ag-pipe installation
 - Site preparation
 - Levelling
 - Soil removal
 - Material delivery
 - Customer-supplied material installation
-

2. BUSINESS MODEL

Berwick Retaining Wall operates under two main models.

MODEL A — SUPPLY + INSTALL

Berwick Retaining Wall can purchase and supply:

- Sleepers
- Posts
- Concrete
- Drainage gravel
- Ag-pipe
- Geotextile fabric
- Screws
- Brackets
- Fixings
- Backfill materials
- Selected capping materials

The business then installs the complete retaining wall according to the agreed scope.

3. MODEL B — INSTALLATION ONLY

The customer supplies the retaining-wall materials.

Berwick Retaining Wall supplies:

- Labour
- Installation equipment
- Standard installation tools

- Levelling
- Positioning
- Post installation
- Sleeper installation
- Fixing
- Cutting
- Alignment
- Final clean-up

The customer must ensure the correct quantity and specification of materials are available before installation.

4. FICTIONAL BUSINESS DETAILS

Business Name: Berwick Retaining Wall

Location: Berwick VIC 3806

Experience: 20 years

Owner: Mark Bennett

Phone: 03 5900 4217

Email: hello@berwickretainingwall.com.au

Website: www.berwickretainingwall.com.au

Trading Hours:

Monday–Friday: 7:00am–5:00pm

Saturday: 8:00am–1:00pm

Sunday: Closed

Quote validity: 14 days

Minimum installation charge: \$650

Site inspection and measure: \$150

Standard service radius: 30 km

Travel outside standard service area: \$95

5. SERVICE AREA

Berwick Retaining Wall services Berwick and surrounding south-east Melbourne suburbs.

Primary areas include:

- Berwick
- Berwick North
- Berwick South
- Harkaway
- Beaconsfield
- Officer
- Pakenham
- Pakenham Upper
- Pakenham South
- Narre Warren
- Narre Warren North
- Narre Warren South
- Cranbourne
- Cranbourne North
- Clyde
- Clyde North
- Hampton Park
- Hallam
- Endeavour Hills
- Lynbrook
- Langwarrin
- Guys Hill
- Koo Wee Rup
- Nar Nar Goon
- Beaconsfield Upper

Jobs outside the standard area may be accepted with an additional travel charge.

Additional travel: \$95

6. RETAINING WALL TYPES

Berwick Retaining Wall can work with several retaining-wall systems.

Timber Sleeper Walls

Timber sleeper retaining walls are commonly used for:

- Garden beds
- Residential landscaping
- Small retaining applications
- Tiered gardens

- Boundary landscaping

Concrete Sleeper Walls

Concrete sleeper walls can be used where a more durable retaining system is required.

Steel Post Systems

Steel posts can be used with compatible concrete or timber sleepers.

Timber Post Systems

Treated timber posts can be used for suitable applications.

The appropriate system depends on:

- Wall height
- Soil
- Ground conditions
- Load
- Drainage
- Location
- Access
- Design requirements
- Engineering requirements where applicable

7. EXACT INSTALLATION PRICES

All prices below are **fictional exact prices**.

No price ranges are used.

Timber Sleeper Installation

Price: \$145 per linear metre

Concrete Sleeper Installation

Price: \$185 per linear metre

Steel Post Retaining Wall Installation

Price: \$195 per linear metre

Timber Post Retaining Wall Installation

Price: \$155 per linear metre

These installation prices assume suitable site conditions and do not automatically include excavation, disposal, engineering, difficult access or additional drainage.

8. SUPPLY + INSTALL PRICING

Timber Retaining Wall Supply + Installation

Price: \$285 per linear metre

Concrete Sleeper Supply + Installation

Price: \$395 per linear metre

Steel Post + Concrete Sleeper Supply + Installation

Price: \$425 per linear metre

Premium Timber Retaining Wall Supply + Installation

Price: \$325 per linear metre

These are fictional standard rates for straightforward projects.

Additional project requirements are quoted separately.

9. WALL HEIGHTS

Retaining-wall pricing is affected by:

- Height
- Length
- Number of posts
- Sleeper type
- Excavation
- Ground conditions
- Drainage
- Access
- Soil pressure
- Surcharge
- Engineering requirements

Common project heights include:

- 300 mm
- 450 mm
- 600 mm
- 750 mm
- 900 mm
- 1,000 mm
- 1,200 mm
- 1,500 mm
- Higher engineered systems where appropriate

A wall should not be priced solely from length if the height or site conditions significantly change the construction requirements.

10. SITE INSPECTION

Site Inspection

Price: \$150

The inspection can assess:

- Wall location
 - Length
 - Height
 - Access
 - Existing wall
 - Soil
 - Drainage
 - Excavation requirements
 - Nearby structures
 - Fencing
 - Trees
 - Services
 - Material access
 - Potential engineering requirements
-

11. MEASUREMENT

During measurement, record:

Wall

- Total length
- Proposed height

- Number of corners
- Steps
- Curves
- Returns
- End points

Ground

- Existing levels
- Finished levels
- Slope
- Soil conditions
- Excavation requirements

Access

- Side access
- Gate width
- Driveway access
- Machine access
- Material access
- Disposal access

12. EXCAVATION

Excavation can be completed manually or with suitable equipment depending on access and site requirements.

Manual Excavation

Price: \$95 per hour

Mini Excavator

Price: \$850 per day

Excavator Mobilisation

Price: \$350

Additional Excavation

Price: \$110 per hour

Major excavation requirements should be separately quoted.

13. POST-HOLE EXCAVATION

Standard Post-Hole Excavation

Price: \$75 per post

Difficult Ground Post Hole

Price: \$125 per post

Difficult ground may include:

- Hard clay
 - Rock
 - Concrete remnants
 - Large roots
 - Existing footings
 - Obstructions
-

14. CONCRETE FOOTINGS

Standard Post Footing

Price: \$95 per post

Heavy-Duty Footing

Price: \$145 per post

Concrete quantity depends on:

- Post dimensions
 - Hole size
 - Wall height
 - Ground conditions
 - Engineering requirements
-

15. DRAINAGE

Drainage is an important part of many retaining-wall installations because water pressure can affect the wall.

Possible drainage components include:

- Ag-pipe
- Drainage gravel
- Geotextile fabric
- Outlet pipes
- Backfill

Ag-Pipe Installation

Price: \$55 per linear metre

Drainage Gravel Installation

Price: \$85 per linear metre

Geotextile Fabric Installation

Price: \$35 per linear metre

Drainage Outlet

Price: \$180 each

Complete Standard Drainage Package

Price: \$650

Actual drainage requirements depend on the site and wall design.

16. BACKFILLING

Standard Backfill Installation

Price: \$75 per linear metre

Compacted Backfill

Price: \$95 per linear metre

Imported Backfill Material

Supply price: \$480

Material quantities are confirmed according to the project.

17. MATERIAL SUPPLY

Berwick Retaining Wall can purchase materials on behalf of customers.

Potential materials include:

- Timber sleepers
- Concrete sleepers
- Steel posts
- Timber posts
- Concrete
- Drainage gravel
- Ag-pipe
- Geotextile fabric
- Fixings
- Capping
- Backfill

Material Procurement Fee

Price: \$180

This covers sourcing, ordering and coordination of standard materials.

18. MATERIAL DELIVERY

Standard Material Delivery

Price: \$250

Large Material Delivery

Price: \$420

Additional Delivery

Price: \$250

Delivery depends on supplier availability and site access.

19. CUSTOMER-SUPPLIED MATERIALS

Customers can supply their own:

- Sleepers
- Posts
- Concrete
- Gravel
- Ag-pipe
- Fabric
- Fixings
- Caps
- Drainage components

Beky Retaining Wall will inspect supplied materials before installation where practical.

Customer responsibility

The customer is responsible for ensuring:

- Correct quantities
- Correct dimensions
- Correct material type
- Correct post system
- Correct sleeper system
- Required fixings
- Compatible components

20. CUSTOMER-SUPPLIED MATERIAL INSTALLATION

If the customer supplies all materials, the installation price covers the agreed labour scope only.

Example:

Concrete sleeper installation: \$185 per linear metre

The customer supplies:

- Concrete sleepers
- Posts
- Concrete
- Drainage materials
- Fixings

unless the written quotation says otherwise.

21. CUSTOMER-SUPPLIED MATERIAL POLICY

Berwick Retaining Wall is not automatically responsible for:

- Incorrect quantities
- Incorrect sleeper dimensions
- Incorrect post sizes
- Damaged sleepers
- Defective materials
- Incompatible components
- Missing fixings
- Incorrect drainage products
- Material colour differences
- Manufacturer defects

If missing or incorrect materials prevent installation, additional attendance may apply.

Return Attendance

Price: \$275

22. TIMBER SLEEPER INSTALLATION

Typical process:

1. Set out wall
 2. Establish levels
 3. Excavate
 4. Mark post positions
 5. Install posts
 6. Concrete posts
 7. Allow appropriate curing time
 8. Install sleepers
 9. Fix sleepers
 10. Check alignment
 11. Install drainage
 12. Backfill
 13. Compact
 14. Final clean-up
-

23. CONCRETE SLEEPER INSTALLATION

Typical process:

1. Measure
2. Set out

3. Establish levels
 4. Excavate
 5. Install posts
 6. Concrete posts
 7. Install concrete sleepers
 8. Check levels
 9. Check alignment
 10. Install drainage
 11. Backfill
 12. Compact
 13. Final inspection
-

24. RETAINING WALL REMOVAL

Timber Retaining Wall Removal

Price: \$85 per linear metre

Concrete Sleeper Wall Removal

Price: \$125 per linear metre

Steel Post Removal

Price: \$95 per post

Timber Post Removal

Price: \$75 per post

Complete Small Wall Removal

Price: \$850

25. DISPOSAL

Timber Disposal

Price: \$480

Concrete Sleeper Disposal

Price: \$650

Mixed Construction Waste

Price: \$550

Soil Disposal

Price: \$720

Disposal prices depend on the agreed quantity and waste type.

26. RETAINING WALL REPAIRS

Possible repairs include:

- Replacing damaged sleepers
- Replacing posts
- Re-fixing sleepers
- Replacing drainage
- Correcting minor sections
- Removing damaged sections

Single Sleeper Replacement

Price: \$180

Timber Post Replacement

Price: \$350

Steel Post Replacement

Price: \$420

Drainage Repair

Price: \$450

Minor Retaining Wall Repair

Price: \$650

27. WALL REPLACEMENT

For an existing wall that has failed or reached the end of its serviceable life:

Typical process:

1. Inspect existing wall
2. Determine replacement scope
3. Remove existing wall
4. Dispose of materials
5. Excavate
6. Install new posts
7. Install sleepers
8. Install drainage
9. Backfill
10. Compact
11. Finish site

A replacement wall should not automatically be quoted as a simple new installation because demolition and disposal may be required.

28. TIERED RETAINING WALLS

Tiered walls may be appropriate for sloping properties where multiple levels are required.

A tiered project may involve:

- Multiple walls
- Separate drainage
- Additional excavation
- Greater material quantities
- Additional backfill
- Greater engineering requirements

Tiered Wall Construction

Price: \$450 per linear metre

This fictional price applies to the installation component for a straightforward tiered system and does not automatically include engineering, major excavation or all materials.

29. RETAINING WALL CAPS

Timber Cap Installation

Price: \$65 per linear metre

Concrete Cap Installation

Price: \$95 per linear metre

Decorative Cap Installation

Price: \$125 per linear metre

Material supply is additional unless specifically included.

30. STEPS IN RETAINING WALLS

Steps may be incorporated into landscaping around a retaining wall.

Standard Retaining Wall Step

Price: \$450 each

Timber Step

Price: \$380 each

Concrete Sleeper Step

Price: \$520 each

31. CORNERS AND RETURNS

Standard Corner

Price: \$180 each

Retaining Wall Return

Price: \$220 each

Complex Corner

Price: \$350 each

32. FENCING ON RETAINING WALLS

A retaining wall may sometimes interact with fencing.

Potential work includes:

- Fence post positioning
- Retaining-wall preparation
- Fence interface
- Post coordination

Fence construction is not automatically included in retaining-wall installation.

Fence Post Interface Preparation

Price: \$180 per section

A separate fencing contractor may be required for the fencing component.

33. SITE ACCESS

Access is an important pricing factor.

Check:

- Gate width
- Side access
- Vehicle access
- Excavator access
- Wheelbarrow access
- Material storage
- Waste removal

Restricted Access Surcharge

Price: \$450

This applies only where the quotation identifies significant additional labour caused by restricted access.

34. ROCKY OR DIFFICULT GROUND

Difficult excavation may involve:

- Rock
- Hard clay
- Existing concrete
- Tree roots
- Old foundations
- Buried waste

Difficult Ground Labour

Price: \$125 per hour

Rock Excavation

Price: \$180 per hour

Additional equipment may be required.

35. SITE CLEAN-UP

Standard Site Clean-Up

Price: \$250

Includes:

- Removal of construction debris
- Basic sweeping
- Collection of offcuts
- General tidy-up

Major soil removal and disposal are separate.

36. STANDARD SUPPLY + INSTALL EXAMPLE

Example fictional project:

20 linear metres

Concrete sleeper supply + installation: \$395/m

$20 \times \$395 = \$7,900$

Standard drainage package: \$650

Material delivery: \$250

Site clean-up: \$250

Total:

\$9,050

This is an example only. The actual quotation would depend on wall height, access, excavation, engineering and site conditions.

37. INSTALLATION-ONLY EXAMPLE

Customer supplies all materials.

Project:

20 linear metres concrete sleeper wall

Installation:

$20 \times \$185 = \mathbf{\$3,700}$

Drainage:

\$650

Clean-up:

\$250

Total:

\$4,600

Materials are supplied by the customer.

38. TIMBER SUPPLY + INSTALL EXAMPLE

Project:

15 linear metres timber sleeper wall

Supply + installation:

$15 \times \$285 = \mathbf{\$4,275}$

Drainage:

\$650

Delivery:

\$250

Clean-up:

\$250

Total:

\$5,425

39. EXACT MASTER PRICE DATABASE

Service	Exact Price
Minimum installation	\$650
Site inspection	\$150
Timber sleeper installation	\$145/m
Concrete sleeper installation	\$185/m
Steel post wall installation	\$195/m
Timber post wall installation	\$155/m
Timber supply + install	\$285/m
Concrete sleeper supply + install	\$395/m
Steel + concrete supply + install	\$425/m
Premium timber supply + install	\$325/m
Manual excavation	\$95/hr
Mini excavator	\$850/day
Excavator mobilisation	\$350
Additional excavation	\$110/hr
Standard post hole	\$75/post
Difficult post hole	\$125/post
Standard footing	\$95/post
Heavy-duty footing	\$145/post
Ag-pipe installation	\$55/m
Drainage gravel	\$85/m
Geotextile fabric	\$35/m
Drainage outlet	\$180

Service	Exact Price
Drainage package	\$650
Standard backfill	\$75/m
Compacted backfill	\$95/m
Imported backfill	\$480
Material procurement	\$180
Standard delivery	\$250
Large delivery	\$420
Return attendance	\$275
Timber wall removal	\$85/m
Concrete wall removal	\$125/m
Steel post removal	\$95/post
Timber post removal	\$75/post
Timber disposal	\$480
Concrete disposal	\$650
Mixed waste disposal	\$550
Soil disposal	\$720
Single sleeper replacement	\$180
Timber post replacement	\$350
Steel post replacement	\$420
Drainage repair	\$450
Minor wall repair	\$650
Tiered wall installation	\$450/m
Timber cap installation	\$65/m
Concrete cap installation	\$95/m
Decorative cap installation	\$125/m
Standard step	\$450
Timber step	\$380
Concrete sleeper step	\$520
Standard corner	\$180
Wall return	\$220
Complex corner	\$350

Service	Exact Price
Restricted access surcharge	\$450
Difficult ground	\$125/hr
Rock excavation	\$180/hr
Site clean-up	\$250

40. QUOTING PROCESS

Step 1 — Customer Enquiry

Collect:

- Name
- Address
- Phone
- Wall length
- Wall height
- Wall type
- New or replacement wall
- Customer supplying materials?
- Desired timeframe
- Access information

Step 2 — Photos

Ask for:

- Full wall area
- Ground slope
- Existing wall
- Side access
- Gate
- Fencing
- Nearby structures
- Trees
- Soil
- Proposed wall location

Step 3 — Site Inspection

Arrange the **\$150 site inspection** where required.

Step 4 — Measure

Confirm:

- Length
- Height
- Levels
- Corners
- Returns
- Access
- Excavation

Step 5 — Determine Wall System

Confirm:

- Timber
- Concrete
- Steel posts
- Timber posts
- Other suitable system

Step 6 — Determine Supply Model

Customer chooses:

Supply + Install

or

Installation Only

Step 7 — Prepare Quote

Itemise:

- Materials
- Labour
- Excavation
- Drainage
- Delivery
- Disposal
- Clean-up
- Other requirements

Step 8 — Approval

Customer approves written quotation.

Step 9 — Deposit

Standard deposit: 30%

Step 10 — Construction

Complete installation according to the agreed scope.

Step 11 — Inspection

Check:

- Levels
- Alignment
- Posts
- Sleepers
- Drainage
- Backfill
- Finish

Step 12 — Completion

Clean site and complete handover.

41. PAYMENT STRUCTURE

Example fictional payment structure:

Deposit: 30%

Progress payment: 40%

Final payment: 30%

Payment terms should be included in the written quotation and applied subject to applicable Australian requirements.

42. VARIATIONS

Variations can include:

- Additional excavation
- Additional drainage
- Unexpected rock
- Additional wall length

- Increased wall height
- Additional disposal
- Additional materials
- Additional steps
- Additional corners
- Customer-requested design changes

Variation Labour

\$110 per hour

Variation Administration

\$75 per approved variation

Variations should be approved before additional work proceeds wherever practical.

43. ENGINEERING & APPROVALS

Retaining walls are not simply landscaping products; the appropriate design depends on factors such as height, soil, loads, drainage and location.

Some projects may require:

- Engineering
- Structural design
- Building approval
- Council approval
- Licensed building work
- Additional documentation

The business should never tell a customer that approval is definitely unnecessary without checking the applicable requirements for the particular project.

Engineering and approval costs are excluded unless specifically included in the quotation.

44. IMPORTANT RETAINING-WALL PRINCIPLE

A retaining wall must be treated as a structural system where applicable.

Important considerations include:

- Wall height
- Soil pressure
- Drainage
- Footings

- Post spacing
- Sleeper strength
- Backfill
- Surcharge loads
- Nearby structures
- Property boundaries
- Slopes

A wall that looks simple from the outside can have significant structural requirements.

45. DRAINAGE PRINCIPLE

Water behind a retaining wall can create pressure.

Potential drainage systems may include:

- Ag-pipe
- Drainage gravel
- Filter fabric
- Outlets
- Suitable backfill

Drainage should be considered during the planning stage rather than treated as an afterthought.

46. CUSTOMER-SUPPLIED MATERIAL CHECKLIST

Before installation:

- ☐ Correct sleepers
 - ☐ Correct number of sleepers
 - ☐ Correct posts
 - ☐ Correct post quantity
 - ☐ Concrete available
 - ☐ Drainage gravel available
 - ☐ Ag-pipe available
 - ☐ Geotextile fabric available
 - ☐ Fixings available
 - ☐ Caps available
 - ☐ Delivery completed
 - ☐ Materials undamaged
 - ☐ Site accessible
-

47. QUALITY CONTROL

Before completion, check:

Posts

- Correct position
- Correct alignment
- Secure
- Appropriate footing

Sleepers

- Correct position
- Level
- Aligned
- Secure

Wall

- Straight
- Correct height
- Correct returns
- Correct corners

Drainage

- Installed where specified
- Pipe positioned correctly
- Drainage gravel installed where specified
- Outlet completed where specified

Backfill

- Appropriate material
- Correctly placed
- Compacted where specified

Final Site

- Construction waste removed
- Offcuts removed
- Ground tidied
- Customer shown completed wall

48. COMMON CUSTOMER QUESTIONS

“Can you supply everything?”

Yes. Berwick Retaining Wall can source the required retaining-wall materials and provide the installation.

“Can I buy the materials myself?”

Yes. Berwick Retaining Wall offers installation-only services for suitable customer-supplied materials.

“Can you install concrete sleepers?”

Yes.

Installation price: \$185 per linear metre

“Can you install timber sleepers?”

Yes.

Installation price: \$145 per linear metre

“Can you supply and install concrete sleepers?”

Yes.

Supply + installation: \$395 per linear metre

“Can you remove my old retaining wall?”

Yes.

Timber wall removal is **\$85 per linear metre**.

Concrete sleeper wall removal is **\$125 per linear metre**.

“Do you do drainage?”

Yes.

The standard drainage package is **\$650**.

“Can you excavate?”

Yes.

Excavation is priced according to the required method and conditions.

“Can you remove the soil?”

Yes.

Soil disposal is **\$720** for the standard fictional disposal allowance.

“Can you build a retaining wall on a boundary?”

Potentially, but the specific site, property boundaries, access, design and applicable requirements need to be assessed before confirming the work.

“Can you build a high retaining wall?”

Potentially, depending on the design and project requirements. Higher or more structurally demanding walls may require engineering and approvals.

49. SALES OBJECTIONS

“I can get the materials cheaper.”

Response:

That's completely fine. Berwick Retaining Wall offers installation-only services, so you can supply the materials yourself and we can quote the installation separately.

“Why is drainage extra?”

Drainage requirements depend on the site and wall design. We separate it from the basic wall installation so the customer can clearly see what is being included.

“Another company quoted less.”

Response:

Compare the scopes carefully. Check whether the other quote includes excavation, footings, drainage, backfill, disposal, delivery and clean-up.

“Can you just give me a price from a photo?”

Response:

Photos can help us understand the project, but the final price may depend on wall measurements, access, ground conditions, drainage and excavation. We can arrange a site inspection for \$150 where required.

50. PHOTO-BASED QUOTING

Photos can help identify:

- Existing wall
- Wall length

- Approximate height
- Slope
- Access
- Existing fencing
- Trees
- Structures
- Drainage conditions

However, photographs cannot reliably reveal:

- Underground conditions
- Soil strength
- Buried services
- Rock
- Existing footings
- Exact levels
- Property boundaries

Therefore, photo-based pricing should be treated as preliminary unless the project is sufficiently straightforward to quote accurately.

51. CUSTOMER JOURNEY

Stage 1

Customer contacts Berwick Retaining Wall.

Stage 2

Project information is collected.

Stage 3

Customer supplies photos.

Stage 4

Initial project assessment.

Stage 5

Site inspection if required.

Stage 6

Measurements confirmed.

Stage 7

Wall system selected.

Stage 8

Supply model selected.

Stage 9

Quotation issued.

Stage 10

Customer accepts quotation.

Stage 11

Deposit paid.

Stage 12

Materials ordered or customer materials confirmed.

Stage 13

Site prepared.

Stage 14

Retaining wall installed.

Stage 15

Drainage and backfill completed.

Stage 16

Quality-control inspection.

Stage 17

Site clean-up.

Stage 18

Final handover.

52. AI CUSTOMER SERVICE RULES

If an AI assistant is used for Berwick Retaining Wall, it should:

1. Always distinguish supply + install from installation-only.
 2. Use exact prices when providing prices.
 3. Never provide price ranges.
 4. Never invent wall measurements.
 5. Never assume a wall is structurally suitable based only on a photo.
 6. Ask for wall length and height.
 7. Ask whether the customer supplies materials.
 8. Ask about access.
 9. Ask whether an existing wall needs removal.
 10. Ask about drainage where relevant.
 11. Flag potential engineering or approval requirements.
 12. Never guarantee that a particular wall system is suitable without assessment.
 13. Clearly separate labour from materials.
 14. Clearly identify disposal charges.
 15. Confirm variations before additional work.
 16. Never promise a start date without confirmation.
 17. Never claim engineering or approval is unnecessary without appropriate confirmation.
 18. Escalate unusual structural conditions.
 19. Treat the written quotation as the controlling project scope.
 20. Never represent fictional prices as legally binding business prices.
-

53. STANDARD CUSTOMER RESPONSE

When a customer asks:

“Can you build a retaining wall?”

Recommended response:

Yes. Berwick Retaining Wall specialises in retaining-wall construction and installation throughout Berwick and surrounding areas. We can either supply the materials and install the wall, or you can supply the materials and we can complete the installation. Our standard timber sleeper installation price is \$145 per linear metre and concrete sleeper installation is \$185 per linear metre. The final quotation depends on the wall height, length, access, excavation, drainage and site conditions.

54. INSTALLATION-ONLY RESPONSE

Yes, we can install a retaining wall using customer-supplied materials. We first confirm the wall length, height, material type, access and site conditions. For a standard timber sleeper wall, installation is \$145 per linear metre, while concrete sleeper installation is

\$185 per linear metre. Additional excavation, drainage, disposal or difficult-ground work is quoted separately.

55. SUPPLY + INSTALL RESPONSE

Yes. Berwick Retaining Wall can source the retaining-wall materials and complete the installation. Our fictional standard supply-and-install price is \$285 per linear metre for a timber sleeper wall and \$395 per linear metre for a concrete sleeper wall. The final quotation is confirmed after assessing the wall height, access, excavation, drainage and site requirements.

56. EXAMPLE PROJECT — CUSTOMER SUPPLIES MATERIALS

Customer wants:

25 metre concrete sleeper retaining wall

Installation:

$25 \times \$185 = \textbf{\$4,625}$

Drainage:

\$650

Excavation:

\$850

Clean-up:

\$250

Total installation project:

\$6,375

Customer supplies the sleepers, posts, concrete and other agreed materials.

57. EXAMPLE PROJECT — BERWICK RETAINING WALL SUPPLIES MATERIALS

Customer wants:

25 metre timber sleeper retaining wall

Supply + installation:

$25 \times \$285 = \textbf{\$7,125}$

Drainage:

\$650

Delivery:

\$250

Clean-up:

\$250

Total:

\$8,275

58. EXAMPLE REPLACEMENT PROJECT

Existing concrete sleeper wall:

18 metres

Removal:

$18 \times \$125 = \textbf{\$2,250}$

New concrete sleeper wall:

$18 \times \$395 = \textbf{\$7,110}$

Drainage:

\$650

Disposal:

\$650

Clean-up:

\$250

Total:

\$10,910

59. 20-YEAR EXPERIENCE POSITIONING

Berwick Retaining Wall should position its experience around:

20 years of retaining-wall construction experience.

Key selling points:

- 20 years of experience
 - Local Berwick service
 - Supply + install
 - Installation-only option
 - Timber retaining walls
 - Concrete sleeper walls
 - Drainage
 - Excavation
 - Repairs
 - Replacement walls
 - Customer-supplied material installation
 - Clear itemised pricing
 - Professional site preparation
 - Final quality inspection
-

60. BUSINESS POSITIONING STATEMENT

Berwick Retaining Wall provides professional retaining-wall construction and installation throughout Berwick and surrounding areas. With 20 years of experience, we can supply the materials and install the complete wall, or install a retaining wall using materials supplied by the customer.

61. FINAL MASTER SUMMARY

Berwick Retaining Wall is a fictional Berwick-based retaining-wall construction business with **20 years of experience**.

The business operates under two primary models:

SUPPLY + INSTALL

Berwick Retaining Wall sources the materials and installs the retaining wall.

INSTALLATION ONLY

The customer supplies the materials and Berwick Retaining Wall completes the installation.

Key exact fictional prices include:

- Site inspection: **\$150**
- Minimum installation: **\$650**
- Timber sleeper installation: **\$145/m**
- Concrete sleeper installation: **\$185/m**
- Steel post installation: **\$195/m**
- Timber post installation: **\$155/m**
- Timber supply + install: **\$285/m**
- Concrete sleeper supply + install: **\$395/m**
- Steel + concrete supply + install: **\$425/m**
- Ag-pipe installation: **\$55/m**
- Drainage package: **\$650**
- Timber wall removal: **\$85/m**
- Concrete wall removal: **\$125/m**
- Standard excavation: **\$95/hour**
- Mini excavator: **\$850/day**
- Material delivery: **\$250**
- Return attendance: **\$275**
- Site clean-up: **\$250**
- Variation labour: **\$110/hour**

The most important distinction is:

CUSTOMER SUPPLIES MATERIALS → BERWICK RETAINING WALL INSTALLS

or

BERWICK RETAINING WALL SUPPLIES MATERIALS → BERWICK RETAINING WALL INSTALLS

The business should always separately identify:

- Materials
- Labour
- Excavation

- Drainage
- Delivery
- Disposal
- Backfill
- Clean-up
- Engineering/approval requirements
- Variations

All prices and business details in this document are **fictional exact prices** and should be replaced with the actual business information before commercial use.

Berwick Retaining Wall — 20 years of retaining-wall construction and installation experience.